









CONCRETE ANCHORAGE REQUIREMENTS				
Anchor Diameter (in)	Minimum Effective Embedment h_{ef} (in)	Minimum Concrete Thickness h_a (in)	Minimum Edge Distance C_a (in)	Minimum Anchor Spacing S (in)
1/2	2	6	6	3

EXPANSION FITTING INSTALLATION POSITION TABLE	
INSTALLATION PERIOD	% OF MAXIMUM EXPANSION RANGE
December to February	80%
March to May and September to November	50%
June to August	20%


- NOTES:
- Expansion fittings and expansion-deflection fittings shall be installed adjacent to BB, EB, joints or hinges (within 8 feet). Fittings must be able to handle up to the Movement Range (MR) noted for the bridge. For expansion fitting installation, see "EXPANSION FITTING INSTALLATION POSITION TABLE."
 - For vault locations and other details not shown, see ROADWAY PLANS.
 - Type 1 conduit continues to vault near bridge.
 - For short overhangs with reduced space, bridging over the drip groove will be allowed as directed by the Engineer.
 - For 2"Ø conduits, a minimum bend radius of 1'-8" is required if the total bend degrees between pull point/vaults is 90 degrees or less. For total bend degrees from 90 to 180, the minimum bend radius for all bend fittings is 2'-0".
 - All mounting hardware shall be protected against corrosion.



PART ELEVATION
NO SCALE



LEGEND:
----- Existing Structure
MEA - Mechanical Expansion Anchor



Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
REGISTERED CIVIL ENGINEER			X	DATE	
PLANS APPROVAL DATE					
THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.					
THE REGISTERED CIVIL ENGINEER FOR THE PROJECT IS RESPONSIBLE FOR THE SELECTION AND PROPER APPLICATION OF THE COMPONENT DESIGN AND ANY MODIFICATIONS SHOWN.					

REGISTERED PROFESSIONAL ENGINEER

No. X

Exp. X

CIVIL

STATE OF CALIFORNIA